

SCOPE OF WORK

Mercado Head Start

Modify Play Area

1. All work is to be prevailing wages.
2. Removals
 - a. 4' X 8' platform and 4' X 4' dollhouse.
 - b. Water table.
 - c. Wooden platform by double doors to gate in fencing.
3. Reduce sandbox to 6' X 6'. Patch asphalt area uncovered by sandbox reduction as required.
4. Patch wooden ramp by gate to close off access on east end.
5. Install concrete walkway from existing sidewalk to gate. To be 4 feet wide.
6. Relocate shed or construct new shed at west end of playground. Will require mounting on railroad ties or concrete posts due to water drainage.
7. Install metal steps with handrails for adults and children from double doors to play area. Patch asphalt as required.
8. Install artificial turf at east end of playground, approx. 20 ft. X 20ft. Prep surface as required.
9. Install 10 ft. X 20 ft. shade structure from edge for poured-in-place to the west.
10. Supply cover for sandbox to prevent access by cats.
11. Install the following stand alone play activities(2006 catalog):
 - a. Number sequencing panel, pg. 73
 - b. Bell panel, pg. 73
 - c. Drum panel, pg. 73
 - d. Driver panel, pg. 74
12. Post bumper required on supports for the shade structure. Canvas construction, 4 feet in height.