

SCOPE OF WORK

Home Ave Head Start Modify Play Areas

Upper Play Area

1. All work is to be prevailing wages.
2. Removals, both areas:
 - a. Small play structure on lower play area.
 - b. PIP fall zone around play structure.
 - c. Stand alone play panels and talk tube.
 - d. Large tire on upper play area.
 - e. Ground cover along east side of bike path. Leave bushes.
 - f. Excavate dirt around upper bike path level with bike path.
3. Provide engineered wood chips around bike path on south, west and north sides. To be level with bike path.
4. Provide four- 2' X 6' flower boxes around bike path.
5. Provide and install play house, approx. 5' X 5' on south side of bike path next to sheds. To have roof, window openings and door.
6. Modify existing sandbox to be in-ground and grade level. To maintain 2 foot distance from bike path surface.
7. Install 10' X 16' shade structure over in-ground sandbox.
8. Install stone or flagstone steps from lower concrete pad to bike path.
9. Plant ground cover plants along east side of bike path.
10. Install 12' X 20' shade structure by shed area.
11. Provide, assemble and install five small tables with benches. To be positioned by center director.
12. Install the following stand alone play activities(2006 catalog):
 - a. Number sequencing panel, pg. 73
 - b. Bell panel, pg. 73
 - c. Drum panel, pg. 73
 - d. Driver panel, pg. 74
13. Post bumper required on supports for the shade structure. Canvas construction, 4 feet in height.

Lower Play Area

1. Provide and install 3 tiered garden boxes, approx. 3 ft. X 6 ft.
2. Install artificial turf from concrete pad to fence and from concrete walkway to bottom of slope. Approx. 1,750 sq. ft.
3. Provide and install two "pride rock" climbing activities or similar activities. Will require fall zone around activities. Incorporate artificial turf over fall zone.
4. Provide and install platform for dramatic play on artificial turf next to concrete pad. Size is to be approx. 10' X 10'. Storage area under platform is a requested feature.
5. Provide and install six simulated "tree stumps" and two simulated "wood logs" for children to sit on. The be located on east side of artificial turf by fence.
6. Provide, assemble and install five benches with back support, approx. 5 feet long.
7. Provide and install shelving in building recess, should be weather-proof.
8. Paint Hop-Scotch design on concrete pad.
9. Install small balance beam on artificial turf along slope of hill. Approx. 2-3 feet from edge of artificial turf.
10. Post bumpers required on supports for the shade structures. Canvas construction, 4 feet in height.
11. Install the following stand alone play activities(2006 catalog):
 - a. Bell panel, pg. 73
 - b. Drum panel, pg. 73

